

STORMWATER DRAINAGE REPORT

**Columbus JACK/Regent
Southpark Place
Grove City, Ohio**

November 4, 2016



AMERICAN
STRUCTUREPOINT
INC.

2550 CORPORATE EXCHANGE DRIVE, SUITE 300
COLUMBIUS, OHIO 43231
614.901.2235

www.structurepoint.com

TABLE OF CONTENTS

1.0	Project Description	2
2.0	Pre-Development Drainage	2
3.0	Post-Development Drainage	2-4
3.1	Critical Storm.....	2-3
3.2	Allowable Release Rates & Detention	3
3.3	Water Quality.....	4
3.4	Storm Sewer.....	4
4.0	Summary and Conclusions	4

Figure 3.1.1	Pre-Developed vs. Post-Developed 1-year, 24-hour Storm Event.....	3
Figure 3.2.1	Post-Developed Stormwater Management Summary	3
Figure 3.3.1	Post-Developed Stormwater Storage Summary	4

Appendix A	Project Location Map
Appendix B	Soils Map
Appendix C	FEMA FIRM 39049C0318K
Appendix D	NOAA Rainfall Data
Appendix E	Pre-Development Tributary Area Exhibit
Appendix F	Pre-Development Runoff Calculations
Appendix G	Post-Development Tributary Area Exhibit
Appendix H	Post-Development Runoff Calculations
Appendix I	Post-Development Water Quality Calculations
Appendix J	Storm Sewer Calculations

Prepared By:



2550 Corporate Exchange Drive, Suite 300
Columbus, Ohio 43231

Registered Engineer

Date

1.0 Project Description

The proposed project is located on Southpark Place, Franklin County, Grove City, Ohio. The development will consist of a 75,000 sq ft warehouse, loading docks, and parking facilities. The total disturbed acreage for the project is 10.964 acres. The retention basin design accounts for all 10.964 acres, which meets the detention requirements of the *Grove City Stormwater Drainage Manual (GCSDM)*

The 10.964 acres of property to be disturbed currently consists of farmed fields, trees, and maintained grass. The existing mounding along the western portion of the property will remain.

An aerial map can be found in Appendix A and a soils map can be found in Appendix B of this report.

2.0 Pre-Developed Drainage

Currently, the 10.964 acres disturbed with this project sheet flows from the property to an existing 24" pipe that exits the east side of the site. The drainage ultimately drains to an unnamed tributary stream of the Scioto River. The pre-developed tributary area consists of farmed fields, trees, and maintained grass, which results in a weighted CN of 81 and a time of concentration (TC) of 24.8 minutes.

Per FEMA FIRM Map Number 39049CV0318K, dated June, 18, 2008, the entire property is located in Zone X, an area determined to be outside of the 0.2% annual chance floodplain. These FEMA FIRM Panel can be found in Appendix C.

NOAA Rainfall Data can be found in Appendix D, a pre-developed tributary area map can be found in Appendix E and pre-developed runoff calculations using HydroCAD Version 10.00 by HydroCAD Software Solutions, LLC can be found in Appendix F of this report.

3.0 Post-Developed Drainage

The post-developed drainage for the 10.964 acres disturbed will outlet into an existing curb inlet located in Southpark Place. The post-developed disturbed area consist of the 75,000 sq ft warehouse, loading docks, parking, walks, and basin, which results in a weighted CN of 90 and a time of concentration (TC) of 13.4 minutes.

A post-developed tributary area map can be found in Appendix G and post-developed runoff calculations using HydroCAD Version 10.00 by HydroCAD Software Solutions, LLC can be found in Appendix H of this report.

3.1 Critical Storm

Per Table 3:1 of the *GCSDM*, the critical storm event was calculated by comparing the pre-developed and post-developed 1-year, 24-hour event using the SCS Type II distribution curve. See figure 3.1.1 below:

Figure 3.1.1 Pre-Developed vs. Post-Developed 1-year, 24-hour Storm Event

Pre-Developed 1-year, 24-hour (af)	Post-Developed 1-year, 24 hour (af)
0.666	1.153

$[(1\text{-year Post-Developed}) - (1\text{-year Pre-Developed})] / [1\text{-year Pre-Developed}] \times 100\% = \% \text{ Increase}$

$[1.153 \text{ af} - 0.666 \text{ af}] / [0.666 \text{ af}] \times 100\% = 73.12\% \text{ Increase (10-year storm event)}$

3.2 Allowable Release Rates & Detention

Per the *GCSDM*, a 73.12% increase in runoff assigns the critical storm as the **10-year storm event**. Additionally, the peak runoff rate for storm events larger than the 10-year storm event will be released at the pre-developed rate for the corresponding year storm event.

Site detention and water quality will be provided by a wet detention basin. As previously mentioned, the storm system outlets into an existing catch basin through a 15" pipe.

A stormwater management summary, including allowable release rates for the project are shown below in figure 3.2.1:

Figure 3.2.1 Post-Developed Stormwater Management Summary

Storm Event	Pre-Developed Area Release Rates (cfs)	Allowable Release Rates (cfs)	Post-Developed Release Rates (cfs)	Detention Release Rates (cfs)	Detention Elevation (feet)
1-Year	7.42	7.42	18.78	1.97	781.28
2-Year	10.77	7.42	24.29	3.67	781.56
5-Year	15.88	7.42	32.20	6.16	781.95
10-Year	20.29	7.42	38.72	6.89	782.32
25-Year	26.68	26.68	47.83	7.79	782.85
50-Year	32.09	32.09	55.36	8.45	783.27
100-Year	37.95	37.95	63.38	9.06	783.69

***Denotes Critical Storm**

Figure 3.3.1 Post-Developed Stormwater Storage Summary

Storm Event (Year)	Volume Required (ac-ft)	Volume Provided (ac-ft)
1	0.146	0.623
2	0.203	0.773
5	0.286	0.994
10	0.352	1.216
25	0.233	1.544
50	0.256	1.820
100	0.280	2.113

3.3 Water Quality

Water quality drawdown per the Ohio EPA NPDES Permit No.: OHC000004 for *large construction activities* has been provided in the proposed retention basin for the entire 10.964 acre tributary area. Per Table 2 of the permit, “Wet Extended Detention Basins” shall provide a drain time of 24-hours. Additionally, the Extended Detention Volume EDv for a “Wet Extended Detention Basin” is to be sized at 75% of the Water Quality Volume (WQv) and the first half of the EDv shall not be released in one-third the drain time. Based on this, the EDv for the proposed basin is 0.411 acre-feet at an elevation of 780.87.

A 4” water quality orifice at elevation 780.00 in the proposed Retention Basin, and has been designed to provide drawdown exceeding 24-hours. Water quality volume calculations can be found in Appendix I of this report.

3.4 Storm Sewer (to be included in with Final Engineering Submittal)

An onsite storm sewer system designed for the 2-year design storm and 5-year check storm will be installed to convey stormwater for the development to the three grated storm structures. All rainfall events, including the 100-year event, are able to be handled by the proposed stormwater system. Routing calculations can be found in Appendix J of this report. In some instances storm sewer is designed to meet the existing conditions of the connection points.


4.0 Summary and Conclusions

The development of this property meets or exceeds Ohio EPA water quality requirements for “large construction activities” and detention requirements per the *GCSDM*.

Accordingly, we believe the proposed improvements will not adversely affect this site, adjacent property owners or Grove City.

Appendix A - Project Location Map

Project Location Map




Appendix B – Soils Data

Soil Map—Franklin County, Ohio
(Columbus JACK)



Map Scale: 1:1,870 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 17N WGS84



**Natural Resources
Conservation Service**

Web Soil Survey
National Cooperative Soil Survey

11/4/2016
Page 1 of 3

Soil Map—Franklin County, Ohio
(Columbus JACK)

MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils



Soil Map Unit Polygons



Soil Map Unit Lines



Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Franklin County, Ohio
Survey Area Data: Version 13, Sep 26, 2015

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 4, 2014—Aug 27, 2014

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Franklin County, Ohio (OH049)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
CrA	Crosby silt loam, Southern Ohio Till Plain, 0 to 2 percent slopes	7.4	65.6%
CrB	Crosby silt loam, Southern Ohio Till Plain, 2 to 6 percent slopes	0.8	6.9%
Ko	Kokomo silty clay loam, 0 to 2 percent slopes	3.1	27.5%
Totals for Area of Interest		11.2	100.0%

Franklin County, Ohio

CrA—Crosby silt loam, Southern Ohio Till Plain, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: 2thy7

Elevation: 520 to 1,550 feet

Mean annual precipitation: 36 to 44 inches

Mean annual air temperature: 48 to 54 degrees F

Frost-free period: 145 to 180 days

Farmland classification: Prime farmland if drained

Map Unit Composition

Crosby and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Crosby

Setting

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, backslope, footslope

Landform position (three-dimensional): Interfluvium, rise

Down-slope shape: Convex

Across-slope shape: Linear

Parent material: Silty material or loess over loamy till

Typical profile

Ap - 0 to 8 inches: silt loam

BE - 8 to 11 inches: silt loam

Bt1 - 11 to 14 inches: silt loam

2Bt2 - 14 to 28 inches: silty clay loam

2BCt - 28 to 36 inches: loam

2Cd - 36 to 79 inches: loam

Properties and qualities

Slope: 0 to 2 percent

Depth to restrictive feature: 24 to 40 inches to densic material

Natural drainage class: Somewhat poorly drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately high (0.01 to 0.20 in/hr)

Depth to water table: About 6 to 24 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 50 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: Low (about 5.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2w

Hydrologic Soil Group: C/D

Hydric soil rating: No

Minor Components

Kokomo, drained

Percent of map unit: 5 percent

Landform: Depressions, swales, water-lain moraines

Landform position (two-dimensional): Toeslope, footslope

Landform position (three-dimensional): Base slope, dip

Down-slope shape: Linear

Across-slope shape: Concave

Hydric soil rating: Yes

Celina, eroded

Percent of map unit: 4 percent

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Side slope, crest, head slope, nose slope, rise

Down-slope shape: Convex, linear

Across-slope shape: Linear, convex

Hydric soil rating: No

Miamian, eroded

Percent of map unit: 1 percent

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Crest, head slope, nose slope, side slope, rise

Down-slope shape: Convex, linear

Across-slope shape: Linear, convex

Hydric soil rating: No

Data Source Information

Soil Survey Area: Franklin County, Ohio

Survey Area Data: Version 13, Sep 26, 2015

Franklin County, Ohio

CrB—Crosby silt loam, Southern Ohio Till Plain, 2 to 6 percent slopes

Map Unit Setting

National map unit symbol: 2thy8

Elevation: 520 to 1,550 feet

Mean annual precipitation: 36 to 44 inches

Mean annual air temperature: 48 to 54 degrees F

Frost-free period: 145 to 180 days

Farmland classification: Prime farmland if drained

Map Unit Composition

Crosby and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Crosby

Setting

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, backslope, footslope

Landform position (three-dimensional): Interfluvium, rise

Down-slope shape: Convex

Across-slope shape: Linear

Parent material: Silty material or loess over loamy till

Typical profile

Ap - 0 to 8 inches: silt loam

BE - 8 to 11 inches: silt loam

Bt1 - 11 to 14 inches: silt loam

2Bt2 - 14 to 28 inches: silty clay loam

2BCt - 28 to 36 inches: loam

2Cd - 36 to 79 inches: loam

Properties and qualities

Slope: 2 to 6 percent

Depth to restrictive feature: 24 to 40 inches to densic material

Natural drainage class: Somewhat poorly drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately high (0.01 to 0.20 in/hr)

Depth to water table: About 6 to 24 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 50 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: Low (about 5.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C/D

Hydric soil rating: No

Minor Components

Kokomo, drained

Percent of map unit: 5 percent

Landform: Depressions, swales, water-lain moraines

Landform position (two-dimensional): Toeslope, footslope

Landform position (three-dimensional): Base slope, dip

Down-slope shape: Linear

Across-slope shape: Concave

Hydric soil rating: Yes

Celina, eroded

Percent of map unit: 3 percent

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Crest, head slope, nose slope, side slope, rise

Down-slope shape: Convex, linear

Across-slope shape: Linear, convex

Hydric soil rating: No

Miamian, eroded

Percent of map unit: 1 percent

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Crest, head slope, nose slope, side slope, rise

Down-slope shape: Convex, linear

Across-slope shape: Linear, convex

Hydric soil rating: No

Lewisburg

Percent of map unit: 1 percent

Landform: Ground moraines, recessional moraines, water-lain moraines

Landform position (two-dimensional): Summit, backslope, footslope

Landform position (three-dimensional): Interfluvium, rise

Down-slope shape: Convex

Across-slope shape: Linear

Hydric soil rating: No

Data Source Information

Soil Survey Area: Franklin County, Ohio
Survey Area Data: Version 13, Sep 26, 2015

Franklin County, Ohio

Ko—Kokomo silty clay loam, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: 2rwj8

Elevation: 820 to 1,140 feet

Mean annual precipitation: 37 to 46 inches

Mean annual air temperature: 48 to 55 degrees F

Frost-free period: 145 to 180 days

Farmland classification: Prime farmland if drained

Map Unit Composition

Kokomo and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Kokomo

Setting

Landform: Depressions on till plains

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Dip

Down-slope shape: Concave

Across-slope shape: Concave

Parent material: Loamy glaciofluvial deposits derived from sedimentary rock over loamy till derived from limestone and dolomite

Typical profile

Ap - 0 to 11 inches: silty clay loam

Btg - 11 to 41 inches: clay loam

Bt - 41 to 64 inches: clay loam

2C - 64 to 79 inches: loam

Properties and qualities

Slope: 0 to 2 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Very poorly drained

Runoff class: Negligible

Capacity of the most limiting layer to transmit water (Ksat):

Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 0 to 6 inches

Frequency of flooding: None

Frequency of ponding: Frequent

Calcium carbonate, maximum in profile: 35 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: High (about 9.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2w

Hydrologic Soil Group: C/D

Hydric soil rating: Yes

Minor Components

Crosby

Percent of map unit: 5 percent

Landform: Till plains

Landform position (two-dimensional): Footslope

Landform position (three-dimensional): Interfluvium

Down-slope shape: Linear

Across-slope shape: Linear

Hydric soil rating: No

Celina

Percent of map unit: 5 percent

Landform: Till plains

Landform position (two-dimensional): Summit

Landform position (three-dimensional): Rise

Down-slope shape: Convex

Across-slope shape: Convex

Hydric soil rating: No

Data Source Information


Soil Survey Area: Franklin County, Ohio

Survey Area Data: Version 13, Sep 26, 2015

Appendix C – FEMA FIRM 39049C0318K



MAP SCALE 1" = 500'



PANEL 0318K

FIRM
FLOOD INSURANCE RATE MAP
FRANKLIN COUNTY,
OHIO
AND INCORPORATED AREAS

PANEL 318 OF 465

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
COLUMBUS, CITY OF	390170	0318	K
FRANKLIN COUNTY	390167	0318	K
GROVE CITY, CITY OF	390173	0318	K

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.



MAP NUMBER
39049C0318K

MAP REVISED
JUNE 17, 2008

Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

Appendix D – NOAA Rainfall Data



NOAA Atlas 14, Volume 2, Version 3
Location name: Grove City, Ohio, USA*
Latitude: 39.8915°, Longitude: -83.0555°
Elevation: 786.98 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnini, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aeriels](#)

PF tabular


PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.354 (0.319–0.394)	0.422 (0.381–0.469)	0.506 (0.456–0.561)	0.572 (0.514–0.631)	0.656 (0.586–0.724)	0.721 (0.642–0.795)	0.785 (0.696–0.864)	0.851 (0.749–0.937)	0.941 (0.821–1.04)	1.01 (0.871–1.11)
10-min	0.550 (0.496–0.612)	0.659 (0.595–0.732)	0.787 (0.709–0.871)	0.883 (0.794–0.974)	1.00 (0.897–1.11)	1.09 (0.973–1.21)	1.18 (1.05–1.30)	1.27 (1.12–1.40)	1.38 (1.21–1.52)	1.47 (1.27–1.61)
15-min	0.675 (0.608–0.750)	0.806 (0.727–0.895)	0.966 (0.870–1.07)	1.09 (0.977–1.20)	1.24 (1.11–1.37)	1.35 (1.20–1.49)	1.47 (1.30–1.62)	1.58 (1.39–1.74)	1.73 (1.51–1.90)	1.83 (1.59–2.01)
30-min	0.893 (0.804–0.992)	1.08 (0.973–1.20)	1.32 (1.19–1.47)	1.51 (1.36–1.67)	1.75 (1.56–1.93)	1.94 (1.72–2.13)	2.12 (1.88–2.33)	2.31 (2.03–2.54)	2.56 (2.23–2.81)	2.75 (2.38–3.02)
60-min	1.09 (0.982–1.21)	1.32 (1.19–1.47)	1.66 (1.50–1.84)	1.92 (1.73–2.12)	2.27 (2.03–2.50)	2.55 (2.27–2.81)	2.84 (2.51–3.12)	3.13 (2.76–3.45)	3.54 (3.09–3.89)	3.86 (3.34–4.24)
2-hr	1.27 (1.15–1.41)	1.54 (1.39–1.70)	1.93 (1.75–2.13)	2.24 (2.03–2.47)	2.68 (2.40–2.94)	3.03 (2.71–3.33)	3.40 (3.02–3.73)	3.79 (3.34–4.15)	4.34 (3.79–4.75)	4.78 (4.14–5.23)
3-hr	1.35 (1.22–1.48)	1.63 (1.48–1.79)	2.03 (1.85–2.23)	2.37 (2.14–2.59)	2.83 (2.55–3.10)	3.21 (2.89–3.51)	3.62 (3.23–3.95)	4.05 (3.58–4.41)	4.65 (4.08–5.07)	5.13 (4.46–5.60)
6-hr	1.61 (1.46–1.77)	1.93 (1.76–2.13)	2.40 (2.18–2.64)	2.80 (2.53–3.06)	3.36 (3.03–3.67)	3.83 (3.43–4.17)	4.34 (3.86–4.71)	4.88 (4.30–5.29)	5.66 (4.93–6.14)	6.30 (5.44–6.84)
12-hr	1.88 (1.71–2.08)	2.26 (2.05–2.50)	2.80 (2.54–3.09)	3.25 (2.94–3.58)	3.90 (3.51–4.29)	4.45 (3.98–4.87)	5.03 (4.47–5.51)	5.66 (4.99–6.18)	6.58 (5.72–7.18)	7.33 (6.31–8.01)
24-hr	2.20 (2.04–2.39)	2.63 (2.44–2.86)	3.24 (3.00–3.52)	3.74 (3.46–4.05)	4.44 (4.09–4.81)	5.02 (4.61–5.44)	5.64 (5.15–6.10)	6.29 (5.70–6.81)	7.20 (6.46–7.81)	7.94 (7.07–8.63)
2-day	2.55 (2.37–2.75)	3.05 (2.83–3.29)	3.72 (3.46–4.01)	4.28 (3.96–4.61)	5.05 (4.66–5.44)	5.68 (5.22–6.13)	6.34 (5.80–6.84)	7.02 (6.39–7.60)	7.98 (7.19–8.66)	8.75 (7.81–9.53)
3-day	2.74 (2.55–2.95)	3.26 (3.04–3.52)	3.98 (3.70–4.29)	4.55 (4.22–4.90)	5.35 (4.95–5.77)	6.00 (5.53–6.47)	6.67 (6.11–7.20)	7.37 (6.72–7.96)	8.34 (7.53–9.03)	9.10 (8.16–9.89)
4-day	2.92 (2.72–3.15)	3.48 (3.24–3.75)	4.23 (3.94–4.56)	4.83 (4.48–5.20)	5.66 (5.24–6.09)	6.33 (5.83–6.81)	7.01 (6.43–7.56)	7.72 (7.05–8.33)	8.69 (7.87–9.40)	9.46 (8.50–10.3)
7-day	3.49 (3.25–3.76)	4.16 (3.87–4.47)	5.03 (4.67–5.40)	5.73 (5.32–6.16)	6.72 (6.20–7.21)	7.51 (6.91–8.06)	8.32 (7.62–8.95)	9.17 (8.35–9.88)	10.4 (9.35–11.2)	11.3 (10.1–12.3)
10-day	3.98 (3.73–4.26)	4.72 (4.43–5.06)	5.66 (5.30–6.05)	6.40 (5.99–6.85)	7.44 (6.93–7.96)	8.26 (7.67–8.84)	9.10 (8.41–9.75)	9.97 (9.17–10.7)	11.2 (10.2–12.0)	12.1 (10.9–13.0)
20-day	5.53 (5.21–5.87)	6.53 (6.15–6.93)	7.68 (7.23–8.15)	8.58 (8.07–9.10)	9.78 (9.17–10.4)	10.7 (10.0–11.4)	11.6 (10.9–12.4)	12.5 (11.7–13.3)	13.7 (12.7–14.7)	14.6 (13.5–15.7)
30-day	6.93 (6.55–7.34)	8.16 (7.71–8.63)	9.48 (8.95–10.0)	10.5 (9.89–11.1)	11.8 (11.1–12.5)	12.8 (12.0–13.5)	13.7 (12.9–14.5)	14.7 (13.7–15.5)	15.8 (14.7–16.8)	16.7 (15.5–17.8)
45-day	8.82 (8.37–9.30)	10.4 (9.82–10.9)	11.9 (11.3–12.5)	13.1 (12.4–13.8)	14.5 (13.7–15.3)	15.6 (14.7–16.4)	16.6 (15.6–17.5)	17.6 (16.5–18.6)	18.7 (17.6–19.9)	19.6 (18.3–20.8)
60-day	10.7 (10.1–11.2)	12.5 (11.8–13.2)	14.3 (13.5–15.0)	15.6 (14.7–16.4)	17.2 (16.3–18.2)	18.5 (17.4–19.5)	19.6 (18.4–20.7)	20.7 (19.4–21.9)	22.0 (20.6–23.4)	22.9 (21.4–24.4)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.


[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves
Latitude: 39.8915°, Longitude: -83.0555°



Average recurrence interval (years)
1
2
5
10
25
50
100
200
500
1000



Duration	
5-min	2-day
15-min	3-day
30-min	4-day
60-min	7-day
2-hr	10-day
3-hr	20-day
6-hr	30-day
12-hr	45-day
24-hr	60-day

NOAA Atlas 14, Volume 2, Version 3

Created (GMT): Tue Nov 1 16:16:23 2016

[Back to Top](#)

Maps & aerals

Small scale terrain



Large scale terrain



Large scale map



Large scale aerial

[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)

Appendix E – Pre-Developed Tributary Area Exhibit


PLOT SCALE: 1"=40' 11/16/16 1:43 PM EDITED BY: NSCHULZE DRAWING FILE: O:\2016\02\23\15.D, DRAWINGS\CIVIL\WORKING DRAWINGS\JUS\2016\02\23\15.CE.DEMO.DWG

EXETER 3405 GANTZ LLC
PID: 040-010038
14.37 ACRES

EXETER 3423 SOUTHPARK, LLC
PID: 040-008991
17.96 ACRES

PIZZUTI LAND LLC
PID: 040-008992
12.22 ACRES

TOSOH SMD LLC
PID: 040-007623
41.16 ACRES



**1,168' Sheet/Shallow
Concentrated Flow**

**10.964 acres
100%pervious
 $T_c = 24.8$ min**

EXETER 3423 SOUTHPARK, LLC
PID: 040-008993
1.76 ACRES

EXISTING LEGEND

EXISTING CONTOUR	---
TREE LINE	~~~~~
RIGHT OF WAY	R/W
GAS LINE	G
WATER LINE	WV
SANITARY SEWER	SS
STORM SEWER	CB
IRRIGATION HEAD	I
TO BE REMOVED	TBR
DO NOT DISTURB	DND
EDGE OF PAVEMENT	EOP

 **Tributary Area**



COLUMBUS JACK / REGENT
SOUTH PARK PLACE
GROVE CITY, OHIO 43123
FOR
COLUMBUS JACK / REGENT
2222 SOUTH THIRD STREET | COLUMBUS, OHIO 43207


PROJECT NUMBER:
2016-02315

ISSUE	DATE
ZONING	NOV. 07, 2016



SHEET:

Pre

Appendix F – Pre-Developed Runoff Calculations



Pre-Development



Routing Diagram for 2016.02315.CE.Detention
Prepared by American Structurepoint, Printed 11/4/2016
HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 1-yr Rainfall=2.20"

Printed 11/4/2016

Page 2


Summary for Subcatchment 1S: Pre-Development

Runoff = 7.42 cfs @ 12.20 hrs, Volume= 0.666 af, Depth> 0.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 1-yr Rainfall=2.20"

Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 2-yr Rainfall=2.63"

Printed 11/4/2016

Page 3


Summary for Subcatchment 1S: Pre-Development

Runoff = 10.77 cfs @ 12.19 hrs, Volume= 0.940 af, Depth> 1.03"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 2-yr Rainfall=2.63"

Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 5-yr Rainfall=3.24"

Printed 11/4/2016

Page 4


Summary for Subcatchment 1S: Pre-Development

Runoff = 15.88 cfs @ 12.19 hrs, Volume= 1.362 af, Depth> 1.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 5-yr Rainfall=3.24"

Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 10-yr Rainfall=3.74"

Printed 11/4/2016

Page 5


Summary for Subcatchment 1S: Pre-Development

Runoff = 20.29 cfs @ 12.19 hrs, Volume= 1.729 af, Depth> 1.89"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 10-yr Rainfall=3.74"

Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 25-yr Rainfall=4.44"

Printed 11/4/2016

Page 6


Summary for Subcatchment 1S: Pre-Development

Runoff = 26.68 cfs @ 12.18 hrs, Volume= 2.267 af, Depth> 2.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 25-yr Rainfall=4.44"

Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 50-yr Rainfall=5.02"

Printed 11/4/2016

Page 7


Summary for Subcatchment 1S: Pre-Development

Runoff = 32.09 cfs @ 12.18 hrs, Volume= 2.728 af, Depth> 2.99"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 50-yr Rainfall=5.02"

Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 100-yr Rainfall=5.64"

Printed 11/4/2016

Page 8


Summary for Subcatchment 1S: Pre-Development

Runoff = 37.95 cfs @ 12.18 hrs, Volume= 3.232 af, Depth> 3.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 100-yr Rainfall=5.64"



Area (ac)	CN	Description
9.857	82	Row crops, contoured, Good, HSG C
1.107	73	Woods, Fair, HSG C
10.964	81	Weighted Average
10.964		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.8	100	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 2.63"
14.0	1,068	0.0200	1.27		Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps
24.8	1,168	Total			

Subcatchment 1S: Pre-Development**Hydrograph**

Appendix G – Post-Developed Tributary Area Exhibit

PLOT SCALE: 1"=40' DATE: 11/16/16 1:45 PM EDITED BY: ASAMUELSON DRAWING FILE: O:\2016\02315\02315 CE GRADING.DWG



COLUMBUS JACK / REGENT
SOUTH PARK PLACE
GROVE CITY, OHIO 43123
FOR
COLUMBUS JACK / REGENT
2222 SOUTH THIRD STREET | COLUMBUS, OHIO 43207

PROJECT NUMBER:
2016-02315

ISSUE	DATE
ZONING	NOV. 07. 2016

SHEET:

Post

Appendix H – Post-Developed Runoff Calculations Overall

STORM SEWER DESIGN - REQUIRED STORAGE VOLUME - TR55

Project: **Columbus JACK**
 Job #: **2016.02315**
 Location: **Grove City, OH**
 Date: **11/04/2016**



AMERICAN
STRUCTUREPOINT
 INC.

Page
 1 of 1

Calc By:
 MJS
 Chk By:
 SLG

Watershed Area (A) =	10.964	ac
Runoff Depth (Q) =	2.2	in
	2.63	in
	3.24	in
	3.74	in
	4.44	in
	5.02	in
	5.64	in

1 yr

2 yr

5 yr

10 yr

25 yr

50 yr

100 yr

Total Post-Developed Site Area in Acres

Value of Runoff Depth Taken From HydroCAD in Post Developed Condition

$$V_r = QA$$

$$V_s = V_r(V_s/V_r)$$

$$q_o = q_i(q_o/q_i)$$

V_r = Runoff Volume

V_s = Storage Volume Required (ac-ft)

V_{sc} = Storage Volume Required (cu-ft)

$$V_s/V_r = C_0 + C_1(q_o/q_i) + C_2(q_o/q_i)^2 + C_3(q_o/q_i)^3$$

$$C_0 = 0.682$$

$$C_1 = -1.43$$


$$C_2 = 1.64$$

$$C_3 = -0.804$$


For Types II and

III Rainfall Distributions



Event	q_i	q_o	V_s	V_{sc}
1	18.78	7.42	0.1463	6371.76
2	24.29	7.42	0.2029	8838.52
5	32.2	7.42	0.2862	12467.91
10	37.72	7.42	0.3522	15340.35
25	47.83	26.68	0.2328	10141.71
50	55.36	32.09	0.2555	11127.80
100	63.38	37.95	0.2796	12179.00



Post Development



(new Pond)



2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 1-yr Rainfall=2.20"

Printed 11/4/2016

Page 2


Summary for Subcatchment 2S: Post Development

Runoff = 18.78 cfs @ 12.05 hrs, Volume= 1.153 af, Depth> 1.26"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 1-yr Rainfall=2.20"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'
					n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 1-yr Rainfall=2.20"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 3

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 1.26" for 1-yr event
 Inflow = 18.78 cfs @ 12.05 hrs, Volume= 1.153 af
 Outflow = 1.97 cfs @ 12.67 hrs, Volume= 0.712 af, Atten= 90%, Lag= 36.8 min
 Primary = 1.97 cfs @ 12.67 hrs, Volume= 0.712 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 781.28' @ 12.67 hrs Surf.Area= 0.531 ac Storage= 0.623 af


Plug-Flow detention time= 253.0 min calculated for 0.711 af (62% of inflow)
 Center-of-Mass det. time= 145.4 min (969.5 - 824.1)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333

Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=1.96 cfs @ 12.67 hrs HW=781.28' (Free Discharge)

- 1=Culvert (Passes 1.96 cfs of 4.72 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.44 cfs @ 5.08 fps)
- 3=Orifice/Grate (Weir Controls 1.52 cfs @ 1.73 fps)
- 4=Orifice/Grate (Controls 0.00 cfs)

Pond 5P: (new Pond)**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 2-yr Rainfall=2.63"

Printed 11/4/2016

Page 5


Summary for Subcatchment 2S: Post Development

Runoff = 24.29 cfs @ 12.05 hrs, Volume= 1.501 af, Depth> 1.64"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 2-yr Rainfall=2.63"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'
					n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 2-yr Rainfall=2.63"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 6

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 1.64" for 2-yr event
 Inflow = 24.29 cfs @ 12.05 hrs, Volume= 1.501 af
 Outflow = 3.67 cfs @ 12.49 hrs, Volume= 1.035 af, Atten= 85%, Lag= 26.1 min
 Primary = 3.67 cfs @ 12.49 hrs, Volume= 1.035 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 781.56' @ 12.49 hrs Surf.Area= 0.550 ac Storage= 0.773 af

Plug-Flow detention time= 210.5 min calculated for 1.035 af (69% of inflow)
 Center-of-Mass det. time= 111.1 min (927.8 - 816.7)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333


Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=3.67 cfs @ 12.49 hrs HW=781.56' (Free Discharge)

- 1=Culvert (Passes 3.67 cfs of 5.66 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.50 cfs @ 5.68 fps)
- 3=Orifice/Grate (Orifice Controls 2.82 cfs @ 3.59 fps)
- 4=Orifice/Grate (Weir Controls 0.35 cfs @ 0.78 fps)

Pond 5P: (new Pond)

Hydrograph



2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 5-yr Rainfall=3.24"

Printed 11/4/2016

Page 8


Summary for Subcatchment 2S: Post Development

Runoff = 32.20 cfs @ 12.05 hrs, Volume= 2.010 af, Depth> 2.20"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 5-yr Rainfall=3.24"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'
					n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 5-yr Rainfall=3.24"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 9

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 2.20" for 5-yr event
 Inflow = 32.20 cfs @ 12.05 hrs, Volume= 2.010 af
 Outflow = 6.16 cfs @ 12.40 hrs, Volume= 1.524 af, Atten= 81%, Lag= 20.8 min
 Primary = 6.16 cfs @ 12.40 hrs, Volume= 1.524 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 781.95' @ 12.40 hrs Surf.Area= 0.578 ac Storage= 0.994 af

Plug-Flow detention time= 179.1 min calculated for 1.524 af (76% of inflow)
 Center-of-Mass det. time= 91.1 min (899.5 - 808.4)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333


Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 ' /' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=6.16 cfs @ 12.40 hrs HW=781.95' (Free Discharge)

- 1=Culvert (Barrel Controls 6.16 cfs @ 5.02 fps)
- 2=Orifice/Grate (Passes < 0.56 cfs potential flow)
- 3=Orifice/Grate (Passes < 3.69 cfs potential flow)
- 4=Orifice/Grate (Passes < 7.89 cfs potential flow)

Pond 5P: (new Pond)

Hydrograph



2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 10-yr Rainfall=3.74"

Printed 11/4/2016

Page 11


Summary for Subcatchment 2S: Post Development

Runoff = 38.72 cfs @ 12.05 hrs, Volume= 2.436 af, Depth> 2.67"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 10-yr Rainfall=3.74"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 10-yr Rainfall=3.74"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 12

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 2.67" for 10-yr event
 Inflow = 38.72 cfs @ 12.05 hrs, Volume= 2.436 af
 Outflow = 6.89 cfs @ 12.41 hrs, Volume= 1.939 af, Atten= 82%, Lag= 21.9 min
 Primary = 6.89 cfs @ 12.41 hrs, Volume= 1.939 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 782.32' @ 12.41 hrs Surf.Area= 0.605 ac Storage= 1.216 af


Plug-Flow detention time= 169.1 min calculated for 1.939 af (80% of inflow)
 Center-of-Mass det. time= 88.8 min (891.9 - 803.0)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333

Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=6.89 cfs @ 12.41 hrs HW=782.32' (Free Discharge)

- 1=Culvert (Barrel Controls 6.89 cfs @ 5.61 fps)
- 2=Orifice/Grate (Passes < 0.62 cfs potential flow)
- 3=Orifice/Grate (Passes < 4.35 cfs potential flow)
- 4=Orifice/Grate (Passes < 17.47 cfs potential flow)

Pond 5P: (new Pond)**Hydrograph**

2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 25-yr Rainfall=4.44"

Printed 11/4/2016

Page 14


Summary for Subcatchment 2S: Post Development

Runoff = 47.83 cfs @ 12.05 hrs, Volume= 3.042 af, Depth> 3.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 25-yr Rainfall=4.44"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'
					n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 25-yr Rainfall=4.44"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 15

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 3.33" for 25-yr event
 Inflow = 47.83 cfs @ 12.05 hrs, Volume= 3.042 af
 Outflow = 7.79 cfs @ 12.44 hrs, Volume= 2.533 af, Atten= 84%, Lag= 23.5 min
 Primary = 7.79 cfs @ 12.44 hrs, Volume= 2.533 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 782.85' @ 12.44 hrs Surf.Area= 0.643 ac Storage= 1.544 af

Plug-Flow detention time= 163.9 min calculated for 2.528 af (83% of inflow)
 Center-of-Mass det. time= 93.2 min (890.0 - 796.8)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333


Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=7.79 cfs @ 12.44 hrs HW=782.85' (Free Discharge)

- ↑ **1=Culvert** (Barrel Controls 7.79 cfs @ 6.35 fps)
- ↑ **2=Orifice/Grate** (Passes < 0.69 cfs potential flow)
- ↑ **3=Orifice/Grate** (Passes < 5.14 cfs potential flow)
- ↑ **4=Orifice/Grate** (Passes < 22.37 cfs potential flow)

Pond 5P: (new Pond)

Hydrograph



2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 50-yr Rainfall=5.02"

Printed 11/4/2016

Page 17


Summary for Subcatchment 2S: Post Development

Runoff = 55.36 cfs @ 12.05 hrs, Volume= 3.550 af, Depth> 3.89"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 50-yr Rainfall=5.02"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 50-yr Rainfall=5.02"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 18

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 3.89" for 50-yr event
 Inflow = 55.36 cfs @ 12.05 hrs, Volume= 3.550 af
 Outflow = 8.45 cfs @ 12.46 hrs, Volume= 3.032 af, Atten= 85%, Lag= 24.8 min
 Primary = 8.45 cfs @ 12.46 hrs, Volume= 3.032 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 783.27' @ 12.46 hrs Surf.Area= 0.674 ac Storage= 1.820 af

Plug-Flow detention time= 164.4 min calculated for 3.032 af (85% of inflow)
 Center-of-Mass det. time= 98.9 min (891.5 - 792.6)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333


Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=8.44 cfs @ 12.46 hrs HW=783.27' (Free Discharge)

↑ **1=Culvert** (Barrel Controls 8.44 cfs @ 6.88 fps)
 ↑ **2=Orifice/Grate** (Passes < 0.74 cfs potential flow)
 ↑ **3=Orifice/Grate** (Passes < 5.69 cfs potential flow)
 ↑ **4=Orifice/Grate** (Passes < 25.60 cfs potential flow)

Pond 5P: (new Pond)

Hydrograph



2016.02315.CE.Detention

Prepared by American Structurepoint

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Type II 24-hr 100-yr Rainfall=5.64"

Printed 11/4/2016

Page 20


Summary for Subcatchment 2S: Post Development

Runoff = 63.38 cfs @ 12.05 hrs, Volume= 4.098 af, Depth> 4.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type II 24-hr 100-yr Rainfall=5.64"

Area (ac)	CN	Description
2.717	80	>75% Grass cover, Good, HSG D
1.664	80	>75% Grass cover, Good, HSG D
0.332	80	>75% Grass cover, Good, HSG D
* 6.251	98	Roof, Paved parking, HSG D
10.964	90	Weighted Average
4.713		42.99% Pervious Area
6.251		57.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Pavement Catch Basin
3.4	1,200	0.0100	5.94	10.50	Pipe Channel, Pipe Flow
					18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38'
					n= 0.013
13.4	1,200	Total			

Subcatchment 2S: Post Development**Hydrograph**

2016.02315.CE.Detention

Type II 24-hr 100-yr Rainfall=5.64"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 21

Summary for Pond 5P: (new Pond)

Inflow Area = 10.964 ac, 57.01% Impervious, Inflow Depth > 4.48" for 100-yr event
 Inflow = 63.38 cfs @ 12.05 hrs, Volume= 4.098 af
 Outflow = 9.06 cfs @ 12.48 hrs, Volume= 3.571 af, Atten= 86%, Lag= 26.1 min
 Primary = 9.06 cfs @ 12.48 hrs, Volume= 3.571 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 783.69' @ 12.48 hrs Surf.Area= 0.706 ac Storage= 2.113 af

Plug-Flow detention time= 166.0 min calculated for 3.571 af (87% of inflow)
 Center-of-Mass det. time= 105.8 min (894.5 - 788.7)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333


Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=9.06 cfs @ 12.48 hrs HW=783.69' (Free Discharge)

↑ **1=Culvert** (Barrel Controls 9.06 cfs @ 7.38 fps)
 ↑ **2=Orifice/Grate** (Passes < 0.79 cfs potential flow)
 ↑ **3=Orifice/Grate** (Passes < 6.20 cfs potential flow)
 ↑ **4=Orifice/Grate** (Passes < 28.52 cfs potential flow)

Pond 5P: (new Pond)

Hydrograph



Appendix I – Post-Developed Water Quality Calculations

WATER QUALITY VOLUME CALCULATIONS

Project: **Columbus JACK**
 Job #: **2016.02315**
 Location: **Grove City, OH**
 Date: **11/1/16**



AMERICAN
STRUCTUREPOINT
 INC.

Page
 1 of 1

Calc By:
 mjs
 Chk By:
 mjs

Wet Basin

Onsite: Subarea A

Area 10.964 acres
 C Value 0.80
 WQ_v 0.548 acre-ft

Onsite: Subarea B

Area 0.000 acres
 C Value 0.40
 WQ_v 0.000 acre-ft

Offsite:

Area 0.000 acres
 C Value 0.40
 WQ_v 0.000 acre-ft

Total WQ_v 0.548 acre-ft
Total 75% WQ_v 0.411 acre-ft

WQ_v Elevation 780.87

Ohio EPA WQ Formula


$$WQ_v = CPA/12$$

$$C = 0.858i^3 - 0.780i^2 + 0.774i + 0.04$$



i = fraction of impervious surface

P = 0.75" precipitation depth

A = drainage area in acres



WQ



2016.02315.CE.Detention

Type II 24-hr 1-yr Rainfall=2.20"

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 2

Summary for Pond 6P: WQ

Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Outflow = 0.35 cfs @ 0.00 hrs, Volume= 0.352 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.35 cfs @ 0.00 hrs, Volume= 0.352 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Starting Elev= 780.87' Surf.Area= 0.502 ac Storage= 0.411 af
 Peak Elev= 780.87' @ 0.00 hrs Surf.Area= 0.502 ac Storage= 0.411 af

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no inflow)

Volume	Invert	Avail.Storage	Storage Description
#1	780.00'	2.333 af	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (acres)	Inc.Store (acre-feet)	Cum.Store (acre-feet)
780.00	0.443	0.000	0.000
781.00	0.511	0.477	0.477
782.00	0.582	0.546	1.024
783.00	0.654	0.618	1.641
784.00	0.729	0.692	2.333


Device	Routing	Invert	Outlet Devices
#1	Primary	780.00'	15.0" Round Culvert L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 780.00' / 779.20' S= 0.0080 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Device 1	780.00'	4.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	781.00'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	781.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.35 cfs @ 0.00 hrs HW=780.87' (Free Discharge)

- 1=Culvert (Passes 0.35 cfs of 2.71 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.35 cfs @ 4.04 fps)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Controls 0.00 cfs)

Pond 6P: WQ

Hydrograph



2016.02315.CE.Detention*Type II 24-hr 1-yr Rainfall=2.20"*

Prepared by American Structurepoint

Printed 11/4/2016

HydroCAD® 10.00-19 s/n 00818 © 2016 HydroCAD Software Solutions LLC

Page 4

Hydrograph for Pond 6P: WQ

Time (hours)	Inflow (cfs)	Storage (acre-feet)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.411	780.87	0.35
0.50	0.00	0.397	780.84	0.35
1.00	0.00	0.383	780.81	0.34
1.50	0.00	0.369	780.79	0.33
2.00	0.00	0.355	780.76	0.32
2.50	0.00	0.342	780.73	0.32
3.00	0.00	0.329	780.71	0.31
3.50	0.00	0.317	780.68	0.30
4.00	0.00	0.304	780.65	0.29
4.50	0.00	0.292	780.63	0.29
5.00	0.00	0.281	780.61	0.28
5.50	0.00	0.269	780.58	0.27
6.00	0.00	0.258	780.56	0.26
6.50	0.00	0.248	780.54	0.26
7.00	0.00	0.237	780.52	0.25
7.50	0.00	0.227	780.49	0.24
8.00	0.00	0.217	780.47	0.23
8.50	0.00	0.208	780.45	0.22
9.00	0.00	0.199	780.43	0.22
9.50	0.00	0.190	780.42	0.21
10.00	0.00	0.182	780.40	0.20
10.50	0.00	0.173	780.38	0.19
11.00	0.00	0.166	780.36	0.19
11.50	0.00	0.158	780.35	0.18
12.00	0.00	0.151	780.33	0.17
12.50	0.00	0.144	780.32	0.16
13.00	0.00	0.137	780.30	0.16
13.50	0.00	0.131	780.29	0.15
14.00	0.00	0.125	780.28	0.14
14.50	0.00	0.120	780.26	0.13
15.00	0.00	0.114	780.25	0.12
15.50	0.00	0.109	780.24	0.11
16.00	0.00	0.105	780.23	0.11
16.50	0.00	0.101	780.22	0.10
17.00	0.00	0.097	780.21	0.09
17.50	0.00	0.093	780.21	0.09
18.00	0.00	0.089	780.20	0.08
18.50	0.00	0.086	780.19	0.08
19.00	0.00	0.083	780.18	0.07
19.50	0.00	0.080	780.18	0.07
20.00	0.00	0.077	780.17	0.06
20.50	0.00	0.075	780.17	0.06
21.00	0.00	0.072	780.16	0.06
21.50	0.00	0.070	780.16	0.05
22.00	0.00	0.068	780.15	0.05
22.50	0.00	0.066	780.15	0.05
23.00	0.00	0.064	780.14	0.05
23.50	0.00	0.062	780.14	0.04
24.00	0.00	0.060	780.13	0.04

Appendix I – Storm Sewer Calculations